

Mount Ascutney Hospital and Health Center Stormwater Improvements Mount Ascutney Regional Commission

REQUEST FOR BIDS – ADDENDUM 1

February 24, 2023

1. The proposed 18” HDPE cross culvert beneath the hospital access road will traverse a known sewer pipe. The exact location and depth of the sewer pipe is unknown. Contractors shall include in their bid the installation of 2” rigid foam insulation beneath the newly installed 18” HDPE culvert for a minimum length of 25 linear feet. The price for installation of the rigid foam insulation shall be included in Item 10 on the updated Bid Form on page 2.

2. Sheet 2 of the drawings includes installation of “fence or guardrail” along the eastern edge of the Hospital parking lot. Sheet 3 of the drawings includes installation of “fence or guardrail” along the shoulder of County Road. These items were not included in the original Bid Form. They have been added to the revised Bid Form on page 2 of this Addendum – see items 5 and 9. This Addendum clarifies that guardrail is required. Contractor shall furnish and install Steel Beam Guardrail per Item 621.20 of the VTrans Standard Specifications for Construction.

3. Areas for Construction Staging were discussed with Hospital staff during the on-site pre-bid meeting. Hospital staff indicated that the area along the eastern edge of the parking lot, outlined below in red, is acceptable for a Contractor Laydown Yard. The final location of the Laydown Yard will be determined in cooperation with the Hospital during a pre-construction meeting.



BID FORM

Base Bid Items:

Project Items	Quantity	Unit Cost	Subtotal
1. Mobilization/Demobilization	1 LS		
2. Install Grass Lined Ditches & Check Dams (BMP 1)	395 LF		
3. Furnish and Install Manhole/Outlet Structure (BMP 1)	1 LS		
4. Install Infiltration Basin, Forebay, and Outlet (BMP 2)	1 LS		
5. Furnish and Install Guardrail along Parking Lot (BMP 1 & 2)	135 LF		
6. Install Pretreatment Grass Swale & Check Dams (BMP 3)	90 LF		
7. Install Stacked Stone Retaining Wall & Drainage (BMP 3)	130 LF		
8. Install Infiltration Basins (BMP 3)	1 LS		
9. Furnish and Install Guardrail along County Road (BMP 3)	130 LF		
10. Furnish and Install 18" HDPE Cross Culvert	50 LF		
11. Site Restoration/Seeding/Mulching	1 LS		
Total Lump Sum Base Bid:			

Company Name _____

Company Address _____

Contact Phone _____

Contact Email _____

Company Reference #1 _____

Company Reference #2 _____

Company Reference #3 _____

Proposal Dated _____

Bidder Name _____

Bidder Signature* _____

***Acknowledgement of Addenda**

In providing this bid proposal, Bidder hereby acknowledges receipt of the following addenda:

Addendum No. _____ Dated _____

Addendum No. _____ Dated _____

Addendum No. _____ Dated _____